Cambridge - CBG

Cambridge Municipal Airport

Associated City: Cambridge, MN
MnDOT Classification: Intermediate Airport
NPIAS Airport: Yes

State Aviation System Plan Facility Needs by Term

Airside Facilities:	Base Year 2010	Short Term 2012 - 2015	Mid-Term 2016 - 2020	Long Term 2021 - 2030
Runway Extension (Feet)	4,000	-	-	-
Runway Widening (Feet)	75	-	-	-
Parallel Txy/Turnaround	Partial	-	Full	-
Runway Lighting	MIRLs	-	-	-
Weather Reporting	Yes	-	-	-
Fuel Capacity (Gal.)	NP	-	-	-
Transient Aircraft Apron (SY)	11,000	15,000	3,000	9,000
Based Aircraft Apron (SY)	-	1,000	-	-
Tie Downs (Each)	-	4	-	-
Navigational Systems:				
Primary R/W Approach Type	Enhanced NPI w/Vertical	-	-	-
Wind Cone	Yes	-	-	-
Rotating Beacon	Yes	-	-	-
PAPIs / VASIs	PAPIs	-	-	-
REILs	Yes	-	-	-
Approach Lighting	None	-	-	-
Airport Buildings:				
Commercial Terminal	No	-	-	-
GA/Administration	Yes	-	-	-
Restroom	No	-	-	-
T-Hangar (Units)	0	0	0	12
Conventional Hangar (Units)	58	0	0	0
Landside Facilities:				
Automobile Parking (Spaces)	18	50	10	20
Perimeter Fencing	Partial	-	-	-

Notes: Data provided is for system planning purposes and shall not be used to justify individual improvement projects.
R/W = Runway, NP = Not Provided.

Source: MnDOT Office of Aeronautics 2011 Inventory Survey and Airport Database & HNTB Analysis.