Perham - 16D

Perham Municipal Airport

Associated City: Perham, MN
MnDOT Classification: Intermediate Airport
NPIAS Airport: No

State Aviation System Plan Facility Needs by Term

Airside Facilities:	Base Year 2010	Short Term 2012 - 2015	Mid-Term 2016 - 2020	Long Term 2021 - 2030
Runway Extension (Feet)	4,100	900	-	-
Runway Widening (Feet)	75	-	-	-
Parallel Txy/Turnaround	Turnaround	-	-	-
Runway Lighting	MIRLs	-	-	-
Weather Reporting	No	-	-	-
Fuel Capacity (Gal.)	NP	-	-	-
Transient Apron (S.Y.)	6,640	1,000	-	2,000
Based Apron (S.Y.)	-	-	-	-
Tie Downs (Each)	-	-	-	-
Navigational Systems:				
Primary R/W Approach Type	Visual/Basic NPI	Enhanced NPI w/Vertical	-	-
Wind Cone	Yes	-	-	-
Rotating Beacon	Yes	-	-	-
PAPIs / VASIs	PAPIs	-	-	-
REILs	Yes	-	-	-
Approach Lighting	None	-	-	-
Airport Buildings:				
Commercial Terminal	No	-	-	-
GA/Administration	Yes	-	-	-
Restroom	Yes	-	-	-
T-Hangar (Units)	15	0	0	0
Conventional Hangar (Units)	4	0	0	0
Landside Facilities:				
Automobile Parking (Spaces)	10	10	-	-
Perimeter Fencing	None	Partial	-	-

Notes: Data provided is for system planning purposes and shall not be used to justify individual improvement projects.

R/W = R/W = Runway, NP = Not Provided.

Source: MnDOT Office of Aeronautics 2011 Inventory Survey and Airport Database & HNTB Analysis.