UNDERWATER BRIDGE INSPECTION REPORT

STRUCTURE NO. 7221

CR NO. 24

OVER

VERMILLION RIVER

DISTRICT 1 – ST. LOUIS COUNTY



PREPARED FOR THE

MINNESOTA DEPARTMENT OF TRANSPORTATION

BY

COLLINS ENGINEERS, INC.

JOB NO. 5221

MINNESOTA DEPARTMENT OF TRANSPORTATION UNDERWATER BRIDGE INSPECTION

REPORT SUMMARY:

The substructure units inspected at Bridge No. 7221, Piers 1 and 2, were found to be generally in good condition. The few defects and areas of soft concrete that were observed are not structurally significant at this time. Scour depressions, 6 feet in radius with 2 feet of depth maximum, were observed at the upstream and downstream columns of Piers 1 and 2. Otherwise, the channel bottom at the bridge appeared stable.

INSPECTION FINDINGS:

- (A) Scaling was observed from 4 feet above the waterline to 1 foot below the waterline with ½ inch maximum penetration at the upstream and downstream columns of Piers 1 and 2.
- (B) Scour depressions 6 feet in radius by a maximum depth of 2 feet were observed at the upstream and downstream columns of both piers.
- (C) A light accumulation of timber debris consisting of logs up to 10 inch in diameter was located at the upstream column of Pier 2 at the channel bottom.
- (D) A moderate accumulation of timber debris consisting of 1 foot diameter and smaller logs and branches was observed at the upstream column of Pier 1 extending from the channel bottom up 2 feet.

RECOMMENDATIONS:

(A) Reinspect the submerged substructure units at the normal maximum recommended (NBIS) interval of five (5) years.

I hereby certify that this plan, specification, or report was prepared by me or under my direct supervision and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

Daniel G. Stromberg

Date <u>6/30/2008</u>

Registration No. 2

Respectfully submitted,

COLLINS ENGINEERS, INC.

Daniel G. Stromberg Registered Professional

Engineer, State of Minnesota

MINNESOTA DEPARTMENT OF TRANSPORTATION UNDERWATER BRIDGE INSPECTION

1. BRIDGE DATA

Bridge Number: 7221

Feature Crossed: Vermillion River

Feature Carried: CR No. 24

Location: District 1 – St. Louis County

Bridge Description: The superstructure consists of a three span, steel girder bridge

supporting a reinforced concrete deck. The superstructure is

supported by two reinforced concrete abutments and two

reinforced concrete column bents. The columns are founded on rectangular footings keyed into bedrock. The piers are numbered 1

and 2, starting from the south end of the bridge.

2. <u>INSPECTION DATA</u>

Professional Engineer Diver: Daniel G. Stromberg, P.E., S.E.

Dive Team: John J. Loftus, Valerie Roustan

Date: August 25, 2007

Weather Conditions: Cloudy, 50° F

Underwater Visibility: 5.0 feet

Waterway Velocity: Negligible/None

3. <u>SUBSTRUCTURE INSPECTION D</u>ATA

Substructure Inspected: Piers 1 and 2

General Shape: The piers consist of a rectangular reinforced concrete pile cap supported

by two concrete columns.

Maximum Water Depth at Substructure Inspected: Approximately 4.1 feet.

4. WATERLINE DATUM

Water Level Reference: The top of the pier cap on the upstream end of Pier 2.

Water Surface: The waterline was approximately 10.6 feet below reference.

Waterline Elevation = 1207.27.

5. NBIS CODING INFORMATION (Minnesota specific codes are used for 92B and 113)

Item 60: Substructure: Code __7__

Item 61: Channel and Channel Protection: Code __7___

Item 92B: Underwater Inspection: Code <u>B/08/07</u>

Item 113: Scour Critical Bridges: Code <u>F/07</u>

Bridge is scour critical because abutment or pier foundation is rated as unstable due to observed scour at bridge site.

_____ Yes <u>X</u> No



Photograph 1. Overall View of Structure, Looking Southwest.




Photograph 2. Overall of Pier 1, Looking Southeast.




Photograph 3. View of Pier 2, Looking Northeast.




Photograph 4. View of Typical Scaling at Upstream Colum of Pier 2, Looking Southwest.





UPSTREAM FASCIA PROFILE



DOWNSTREAM FASCIA PROFILE

Note:

Refer to Figure 1 for General Notes.

MINNESOTA DEPARTMENT OF TRANSPORTATION UNDERWATER BRIDGE INSPECTION

STRUCTURE NO. 7221 OVER THE VERMILLION RIVER DISTRICT 1, ST. LOUIS COUNTY

UPSTREAM AND DOWNSTREAM FASCIA PROFILES

Drawn By: PRH Checked By: DGS

- COLLINS 123 North Wacker Drive Suite 300
- ENGINEERS 2 (317 704-9300)
- www.collinsengr.com
- Engineers 2 (317 704-9300)
- Figure No.: 2 Code: 52210014

MINNESOTA DEPARTMENT OF TRANSPORTATION OFFICE OF BRIDGES AND STRUCTURES DAILY DIVING REPORT

INSPECTORS: Collins Engineers, Inc. DATE: August 25, 2007
ON-SITE TEAM LEADER: <u>Daniel G. Stromberg, P.E., S.E.</u>
BRIDGE NO: 7221 WEATHER: Cloudy, 50° F
WATERWAY CROSSED: Vermillion River
DIVING OPERATION: X SCUBA SURFACE SUPPLIED AIR
OTHER
PERSONNEL: John J. Loftus, Valerie Roustan
EQUIPMENT: Scuba, Scraper, Lead Line, Sounding Pole, Probe Rod, Camera
TIME IN WATER: 2:00 p.m.
TIME OUT OF WATER: 2:20 p.m.
WATERWAY DATA: VELOCITY <u>Negligible / None</u>
VISIBILITY 5.0 feet
DEPTH 4.1 feet maximum at Pier 2
ELEMENTS INSPECTED: Piers 1 and 2
REMARKS: Overall, concrete was smooth and sound. Scaling was observed 4 feet above
the waterline to 1 foot below the waterline at the upstream and downstream columns of
Piers 1 and 2. Scour depressions, 6-foot-radius by a maximum depth of 2 feet, were
observed at the upstream and downstream columns of both piers. Light to moderate
accumulations of timber debris was observed at the upstream columns of Piers 1 and 2.
FURTHER ACTION NEEDED: YES X NO
Reinspect the submerged substructure units at the normal maximum recommended (NBIS) interval of five (5) years.

MINNESOTA DEPARTMENT OF TRANSPORTATION OFFICE OF BRIDGES AND STRUCTURES

UNDERWATER INSPECTION CONDITION RATING FORM

BRIDGE NO. 7221		INSPECTION DATE August 25, 2007	
INSPECTORS Collins Enginee	ers, Inc.	NOTE: USE ALL APPLICABLE CONDITION	
ON-SITE TEAM LEADER.	Daniel G. Stromberg, P.E., S.E.	DEFINITIONS AS DEFINED IN THE MINNESOTA	
WATERWAY CROSSED	Vermillion River	RECORDING AND CODING GUIDE INCLUDING	

CO	N	\Box	ΙT	\cap	N	R	ΔΤ	IN	
(,()	IV			IV)	ıv	-	\sim 1	111	כאו

				SUBSTRUCTURE					CHANNEL					GENERAL					
UNIT REFERENCE NO.		MAXIMUM DEPTH OF WATER	PILING	COLUMNS, SHAFTS, OR FACES*	FOOTINGS	DISPLACEMENT	ОТНЕК	OVERALL SUBSTRUCTURE CONDITION CODE*	SCOUR	EMBANKMENT EROSION	EMBANKMENT PROTECTION	OTHER (DRIFT/DEBRIS)	OVERALL CHANNEL & PROTECTION CONDITION	CONCRETE	STEEL	TIMBER	LOSS OF SECTION	PREVIOUS REPAIR OR MAINTENANCE	ОТНЕК
	UNIT DESCRIPTION	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18
	Pier 1	3.9'	N	7	N	9	N	7	7	8	8	7	7	7	N	N	N	N	N
	Pier 2	4.1'	N	7	N	9	N	7	7	8	8	7	7	7	N	N	N	N	N
																		D DODIN	

*UNDERWATER PORTION ONLY

GENERAL, SUBSTRUCTURE, CHANNEL AND PROTECTION. AND CULVERTS AND WALL DEFINITIONS TO COMPLETE THIS FORM.

REMARKS: Overall, concrete was smooth and sound. Scaling was observed 4 feet above the waterline to 1 foot below the waterline at the upstream and downstream columns of Piers 1 and 2. Scour depressions, 6-foot-radius by a maximum depth of 2 feet, were observed at the upstream and downstream columns of both piers. Light to moderate accumulations of timber debris was observed at the upstream columns of Piers 1 and 2.

ATTACH SKETCHES AS NEEDED, IDENTIFY REMARK BY REFERRING TO UNIT REFERENCE NO. AND REMARK NO. NOTES: USE GENERAL SECTION TO IDENTIFY OVERALL PRESENCE OF SPALLS, CRACKS, CORROSION, ETC.